



# X-326 Sampling Analysis Plan

## Compressor Removal

Once the converters are removed, work begins on the compressors.



Compressors are housed within a heated enclosure for temperature control.



Enclosure is removed for easy access.



Compressor detached from interconnecting piping using a plasma torch.



Metal plates are welded to secure the openings.



Compressor is lifted from the cell housing



Compressor is lowered to the Operating floor to await shipment to the Nevada National Security Site (NNSS) for disposal.