



WHAT DOES DECOMMISSIONING INVOLVE ?

Decontamination and Decommissioning Facilities



- Three separate process buildings (X-326, X-330, X-333) total 96 acres (about 200 football fields of floor space under roof). If these buildings are removed, these steps would be taken.
 - Remove hazardous material such as lubricating oils and mercury switches
 - Dismantle and remove the radiologically contaminated process equipment
 - Remove asbestos within the buildings
 - Deactivate the utilities (heat, light, water)
 - Remove exterior asbestos siding
 - Demolish the structure
- Plant support facilities that are no longer needed will be removed.
- Utilities (steam, power, and water) must be altered and optimized to support other site tenants (American Centrifuge Project and Uranium Disposition Services).



Lube Oil Removal



Electrical Capacitor Removal

OUR SITE.
OUR FUTURE.

